



HRT-24v

RUN TIMER

(240v version also available)

30min. ~ 2Hr. DELAY OFF TIMER

- 24vAC Powered & Manufactured to Australian Standards.
- 4 Time delay settings : 1min, 30min, 1Hr, & 2 Hr.
- 8amp (res.) potential free relay output.
- Indication Led flashes during timing.
- Potential Free 240v 8 Amp rated Relay Output.
- Toggle On / Toggle Off selection jumper.
- Version available with external inputs for Run & Fault Indication.
- Built using standard CLIPSAL 2000 wall plate.

